



North Eastern Indira Gandhi Regional Institute of Health and Medical Sciences
(An Autonomous Institute, Ministry of Health and Family Welfare, Government of India)
Director's Block, Mawdiangdiang, Shillong 793 018 (Meghalaya)

Website: www.neigrihms.gov.in

Tender No: CVENGG /11/2026 -Engg (C):

Dated 9th July, 2026

TENDER /BID DOCUMENT

**ONLINE OPEN E- TENDER ARE INVITED FROM REGISTERED CONTRACTORS OF
PWD/ PHE/ ESTATE OFFICE (GAD)/ MES/ MeECL AND EQUIVALENT CLASS OF
CPWD FOR RENOVATION OF POLICE OUTPOST OFFICE INCLUDING CIVIL,
PLUMBING AND PAINTING WORKS
(e -Procurement)**

Bid Document Downloading Start Date:	1400 hours of 10.7.2026
Last Date and Time for Submission of Bid Document Online:	1400 hours of 23.7.2026
Last date and Time of Receipt of Earnest Money Deposit (hard copies):	1400 hours of 23.7.2026
Date and Time of Opening of Techno -Commercial Bids:	1400 hours of 24.7.2026
Cost of Earnest Money Deposit (EMD):	Rs.67,300/-

Bidders /Tenderers can download the tender /bid document from Central Public Procurement Portal website at www.eprocure.gov.in Bidders /Tenderers are required to submit their bid online by uploading all the relevant documents through www.eprocure.gov.in

Tender document can also be downloaded from the Institute's website at www.neigrihms.gov.in For further details regarding amendment /addendum /extension please visit website: www.eprocure.gov.in and www.neigrihms.gov.in

In the event of the date being declared as a closed holiday for purchaser's office, the due date for submission of bids online and opening of bids online will be the following working day at the appointed time.

DETAILED TENDER NOTICE

Online tenders in two bid systems are invited from registered contractors of PWD/PHE/Estate office (GAD)/MES/MeECL and equivalent class of CPWD for the following work.

Name of work	Estimated cost (Rs) (approx)	EMD (Rs)
Renovation of Police Outpost Office Including Civil, Plumbing and Painting Works	Rs. 33,65,020/-	Rs.67,300/-

General Conditions of Contract (GCC):

1. Bidders /Tenderers would be required to register on the Central Public Procurement Portal at www.eprocure.gov.in, using a valid Digital Signature Certificate (DSC) and valid email address to be able to participate in the bidding process. On registration with the Portal they will be provided with a user id and password by the system through which they can submit their bids online.
2. Digital Signature Certificate (DSC) may be obtained from any authorized agencies registered with the Certifying Authority (CA), through National Informatics Center (NIC) in India.
3. Bidders /Tenderers can download the bid document from Central Public Procurement Portal website at www.eprocure.gov.in Bidders /Tenderers are required to submit the signed tender documents as part of acceptance of the T&C of the tender ,online by scanning and also uploading all relevant documents through www.eprocure.gov.in
4. Tender document can also be downloaded from the Institute's website at www.neigrihms.gov.in For further details regarding Amendment /Addendum /Extension please visit website: www.eprocure.gov.in and www.neigrihms.gov.in
5. **Earnest Money Deposit (EMD) in the form of Call deposit, Banker's Cheque, Fixed deposit or Demand draft, drawn in favour of NEIGRIHMS EMD Security Deposits** or Bank Guarantee of any Scheduled Bank, shall be scanned and submitted online, along with the Techno-commercial bid (Un priced Bid), within the period of tender online submission date and time and the original (hard copy) should be dropped in the tender box in the Engineering Section, Director's Block, Mawdiangdiang, NEIGRIHMS, Shillong -793018, **not later than the last date of e-submission of the tender**
6. The technical bids will be opened online by a committee of members duly constituted for the purpose at the time and date as specified in the tender document. All statements, documents, certificates, Affidavits, etc uploaded by the bidders will be verified and downloaded for technical evaluation and the result of technical bid evaluation will be displayed on www.eprocure.gov.in which can be seen by all bidders who participated in the tender.
7. The bidders should download the **BoQ.xls** from CPP Portal and filled in the blank spaces provided for mentioning the name of bidder and rates. Bidders cannot modify any other text or background shown in the BOQ template or replace it with any other copy of same **BOQ in .xls format**. NEIGRIHMS /Central Public Procurement Portal (www.eprocure.gov.in) will accept the BOQ template only and hence the rate should not be quoted in any other place except BOQ template.
8. The Financial bid (price bid) i.e. Bill of Quantity (BOQ) of only technically qualified bidders will be opened online by a committee of members and the result will be displayed on the www.eprocure.gov.in which can be seen by all bidders who participated in the tender.
9. **Contractor shall quote the rate of AT PAR or ABOVE the Meghalaya PWD Schedule of Rates for buildings 2021 – 22 / for Roads 2020 – 21 and as per prevailing market rate for the Non Schedule Items.**
10. **Institute will reject Bids with rates quoting BELOW, the estimated value put to tender, for scheduled items.**
11. The site is located at Mawdiangdiang
12. Time of completion: 6 (six) months from the date of issue of commencement order.
13. Contractors shall be deemed to have inspected and examined the site of work and its surroundings and familiarized themselves, before submitting the tenders.
14. Tenderers will have to submit copy of their registration, which is valid as on the last date of bid submission.
15. The contractor shall not sub-contract the work to sub-contractors or to any single sub-contractor. An undertaking by the contractor shall have to be submitted to this effect.
16. The successful contractor shall provide a performance security for his proper performance of the contract within 7 (seven) days from the date of receipt of letter of award. **The performance Security shall be in the form of FD/Call Deposit to be pledged in favour of NEIGRIHMS EMD Security Deposits.** The amount of the security shall be 5% (five percent) of the contract price. The performance security shall remain valid for a minimum period of sixty days beyond the date of completion of all contractual obligations and shall be returned to the contractor within 14 days after expiry of the performance security. If the contractor fails to perform the work as per terms and conditions of the contract, the performance security shall be forfeited at his own risk and responsibility.
17. If during the execution of the work the contractor encounters physical obstructions or physical conditions other than climatic conditions on the site, which obstructions or conditions were in his reasonable opinion not foreseeable by the contractor, the contractor shall forth with give notice thereof to the Superintending Engineer, NEIGRIHMS. On receipt of such notice, the SE shall, in his opinion feel that such obstructions/conditions could not have been reasonably foreseen by the contractor, after due consultation with the contractor determine any extension of time with no financial bearing to which the contractor is entitled.
18. During the execution of the works, the contractor shall keep the site reasonably free from all unnecessary obstructions and shall store or depose of any contractors equipment and surplus materials and clear from the site any wreckage, rubbish or temporary works in consultation with the Sanitary Supt of the Institute.
19. Before issue of any completion certificate, the contractor shall clear away and remove from that part of the site to which the completion certificate relates all contractors' equipment, surplus material, rubbish and temporary works of every kind.
20. The contractor while employing labour should ensure that all the statutory labour laws and regulations are adhered to

21. In the event of
 - a. The amount or nature of extra or additional work
 - b. Exceptionally adverse climatic conditions
 - c. Other special circumstances which may occur other than through a default or breach of contract by the contractor or for which he is responsible. Being such as fairly to entitle the contractor to extension of time for completion of the works or any section or part thereof, the Institute shall after due consultation with the contractor and subject to clause 17 determine the amount of such extension with no financial bearing and shall notify the contractor accordingly.
22. If the contractor fails to complete the execution and completion of the works as specified in the work order, the contractor shall be bound to pay as liquidated Damages a sum of 0.5 % (percent) per week of delay for such default subject to a maximum of 5 % of the contract price.
23. When whole of the works have been substantially completed, the contractor shall give a notice to the Superintending Engineer of the Institute, accompanied by a written undertaking to finish with due expedition any outstanding work during the defect Liability period. Such notice and undertaking shall be deemed to be a request by the contractor to the SE to issue a taking over certificate.
24. Defect liability period shall be 12 (twelve) months calculated from the date of completion of the works certified by the SE in the completion certificate.
25. The performance bank guarantee shall be kept valid for a period of 6(six) months after the DLP.
26. If the contractor fails to fulfill any of the obligations under this contract, the Institute shall be at liberty to terminate the contract thereby voiding the contract and will be at liberty to allot the whole work or balance works to any other party at the risk and cost of the first party.
27. All works are to be carried out as per current specification prevailing in the state of Meghalaya (MPWD & CPWD) and when directed by the Institute.
28. Institute is adopting Scheduled of Rates of Meghalaya State –PWD for roads & building. **There will be no price escalation whatsoever. The rates quoted by the successful bidder on acceptance by the Institute, will be binding and final.**
29. **Average Annual Financial Turnover** during the last five years ending 31st March of the previous financial year should be at least **30 % of the estimated cost**. Tenderer to submit Financial Statement **ONLY** from Chartered Accountant as per **Annexure – I**.
30. Parties should have the experience of having successfully completed **similar works** during the last **5 (five) years** ending last day of month previous to the one in which applications are invited should be either of the following: (a) **Three similar completed works each** costing not less than the amount equal to **40% of the estimated cost** or (b) **Two similar completed works each** costing not less than the amount equal to **50 % of the estimated cost** or (c) **one similar completed work** costing not less than the amount equal to **80 % of the estimated cost**.
31. Documentary proof in the form of **work orders and completion certificates** are to be enclosed failing which the tender will be non-responsive.
32. Completion Certificates should indicate items of works executed along with date of award of work & time of completion as per work order & actual time of completion and are to be signed by Officers not below the rank of **Executive Engineers or Equivalent (Annexure –II)**
33. List of completed works as per Clause 32, should be submitted year wise (Last 5 Years) at **(Annexure – III)**
34. List of Ongoing works during last 5(five) years along with value , % completion and Time of Completion be submitted at **(Annexure –IV)**
35. **AVAILABLE BID CAPACITY**
 Applicants who meet the minimum qualification criteria will be qualified only if their available bid capacity at the expected time of bidding is more than the total estimated cost of the work. The available bid capacity will be calculated as under:
Available Bid Capacity = (A x N x 2 – B), where:
A -Maximum value of engineering (Civil/ Electrical/ Mechanical as relevant to work being procured) works **executed in any one year** during the last five years (updated at the current price level), considering the completed as well as works in progress (90%)- Substantially completed works :-
 “means an ongoing work in which payment equal to or more than 90% of the present contract value has been made to the contractor in that ongoing contract, and the work or a major part of it is in a usable condition for its intended purpose
B -Value of work at current price level of the existing commitment and outgoing work to be completed during the period of completion of work for which are invited.
N -Number of years prescribe for completion of the works for which the bid are invited is the number of years prescribed for completing the works
36. Running payments can be made to the contractor subject to certification by the Superintending Engineer after completion of about 50% of the work and final payment will be paid after completion of the work after due certification and satisfaction of the Superintending Engineer.
37. Parties to submit PAN Card, GST Registration, valid Labour License from Labour Department
38. Rates once accepted will not be enhanced due to variation in the rate of materials, labour and Government taxes.
39. Bidder should submit documents showing that they have enough plant and machineries. Undertaking in the form of affidavit to be submitted. No tools and plants will be supplied by the Institute
40. No materials will be supplied by the Institute.
41. The quoted rates shall be firm, fixed and binding on the contractor irrespective of any variation in the quantities stated in the contract upto $\pm 15\%$ variation of the contract value as a whole.
42. Successful Non –Tribal tenderers should submit the valid Trading license within 14 (fourteen) working days from the date of issue of preliminary work order, failing which the order shall be withdrawn at their risk and responsibility. Trading License submitted should be specifically for similar nature of work for which the tender is called for.
43. **In case of dispute:** It is agreed between the first party and the second party that all disputes, differences and claims whatsoever which shall arise at any time between the parties hereto or their respective representatives concerning this contract and all other documents in pursuance hereof as to the rights, duties, obligations or liabilities of the parties hereto respectively by virtue of this contract shall be referred to the Director of the Institute, which shall then take a final call on the matter and will be final and binding.
44. The specifications and mode of measurement for civil works shall be in accordance with PWD specifications unless otherwise specified and more specifically as per approved Drawing, Specification and Estimate.

45. **In the event of responsive parties quoting same rates and having same Available Bid Capacity, Institute reserves the right to either allot the work to the bidder having higher / highest credentials in terms of Similar Work experience or at the discretion of the Institute based on past experience and performances of the responsive bidder/ bidders etc and decision of Institute will be final.**
46. If there is any excess payment on any item etc made to the contractor, the contractor shall not hesitate to cooperate in adjusting / deducting the same from either the running bills or final bills.
47. **The Institute reserves the right to accept or reject any or all tenders without assigning any reason thereof**
48. All the above requirements are compulsory for fulfillment as part of the tenders failing which tenders will be rejected.
49. All documents, registrations should be valid as on the last date of tender.
50. Taxes as applicable will be deducted from the bills of the contractor.
51. Parties to submit the list of technical staff with at least 1(one) experienced Junior Engineer-Civil (Diploma). Attested copy of diploma/degree certificates to be enclosed. Undertaking in the form of affidavit to be submitted.
52. The parties to furnish an affidavit on a non-judicial stamp paper that there is no police/vigilance/CBI case pending against them.
53. Successful bidder will have to furnish an Undertaking to carry out/ execute the work in strict conformity to the specifications as mentioned in the scheduled items and guide notes of the Scheduled of Rates and Indian Standard codes of practice for materials / as per direction of the Engineer-in-charge failing which he/she shall be liable for disqualification/ blacklisted from participating in future tenders of NEIGRIHMS
54. **The Party shall be responsible for the safety of all its workmen/employees during the period of execution of the work. The party shall provide all safety materials, insurance cover, gadgets, equipment etc to all its workmen/employees to ensure their safety during execution of the work. The Institute shall not be held responsible in case of any accidents, mishaps etc to the party and its employees**
55. Any delay in completion of the works beyond the stipulated date due to reasons attributable to the contractor may eventually lead to cancellation of letter of award for which the contractor is not entitled to any compensation. The cancellation of letter of award would lead to forfeiture of performance security.
56. **The contractor is to register with the Labour Department for the work and the registration certificate has to be submitted, failing which the bill cannot be processed**
57. If any statutory tax/deduction/recovery is notified by the State/Central Govt, the same shall be deducted from the bill of the contractors as applicable from its effective date of coming into force.
58. The Payment for the work done by the Contractor will be on the basis of measurement of the work executed. **The Contractor's Engineer or his authorized agent or representative shall be present at the time of recording of each set of measurements and sign on the measurement book as a token of acceptance of the measurement.**
59. Contractors who engage / employ five or more Inter State Migrant Workmen is required to obtain a license from District Labour Office, East Khasi Hills, Shillong as per prevailing labour laws applicable in the State.
60. Bidders should note that the above terms and conditions will apply specifically in addition to the rules / regulations applicable to works in the Government of India.
61. **All prevailing GFR rules will be applicable and binding.**
62. Wherever relevant, water charges @ 1% on the Order value will be as applicable or Contractor may arrange his / her own water supply with intimation to the Executive Engineer.
63. Electricity charges when used by the Contractor will be deducted from the bill as per actual usage/consumption through tested meter in consultation with Electrical Department of the Institute or the Contractor may use his / her own DG sets in case of fabrication works etc , with intimation to the Executive Engineer.
64. Forest Royalty of stone and sand shall be deducted as per latest / prevailing rate of Forest Department Government of Meghalaya
65. **In the event that structural / architectural design is required, the qualified bidder shall at his own cost provide the structural / architectural design from reputed structural engineers / firms and submit to the Institute for acceptance.**
66. **For concrete / RCC works, contractor will have to carry out standard cube tests before and after casting of any RCC member at the cost of the contractor.**
67. **The court jurisdiction for any dispute, if not settled as per Clause 43, shall be at Shillong, Only.**

Sd/
Superintending Engineer -NEIGRIHMS

Check List of documents to be submitted along with the tender:

Sl No	Documents	Remarks
1	Tender documents	
2	Earnest money Deposit	
3	Copy of registration	
4	Undertaking not to sub-let the work. (format enclosed with the tender)	
5	Pan Card.	
6	G S T certificate	
7	Valid Labour License	
8	Documentary proof of work orders, completion certificates as specified in clause 30 of the GCC.	
9	Completion certificates as per FORMAT – A	
10	Average Annual Financial Turnover during the last five years as per FORMAT - B	
11	List of technical staff with Undertaking in the form of affidavit (Degree/Diploma certificate to be enclosed)	
12	Affidavit of no vigilance/police/CBI case pending against them	
13	Plant and machineries. Undertaking in the form of affidavit	

FORM OF UNDERTAKING

To

The Superintending Engineer
NEIGRIHMS

Sub: Renovation of Police Outpost Office Including Civil, Plumbing and Painting Works

Sir,

With reference to the above, I hereby undertake not to sublet the work cited above, if the work is allotted to me.

*Name of contractor	
*Full postal Address	
*Email Address	
*Mobile No	
*Alternate Mobile No	
*Signature and Seal	

All the fields marked * above are mandatory to be furnished by the contractor

Annexure - II.

1. Name of Contractor: -
2. Name of work completed: -
3. Agreement No: -
4. Name of Division in which work was executed: -
5. Tender Cost: -
6. Stipulated date of Start (as per w/o):-
7. Stipulated date of Completion (as per w/o):-
8. Actual date of Completion: -

Signature of Contractor

**Signature of Officer issuing the C/Certificate

** (Officer should not be lower than the rank of Executive Engineer – Civil)

List of completed works in last 5 (five) Years - Annexure – III

Sl No	Name of Work	Value of Work in Rs					Date / Month / Year of completion
		2020-21	2021-22	2022-23	2023-24	2024-25	
Total value of Works / Year in Rs							

List of all Ongoing Works last 5(five) years – Annexure –IV

[illegible]

FINANCIAL STATEMENT - Annexure – I

SL NO	FINANCIAL PERIOD	AMOUNTS IN LAKHS
1.	2021 - 2022	
2.	2022 - 2023	
3.	2023 - 2024	
4.	2024 - 2025	
5.	2025 - 2026	

**Signature Of
Contractor**

**Signature & Seal
Chartered Accountant**

I, Shri _____, son of Shri _____,
_____ aged about _____, resident of

_____ do hereby solemnly affirm and declare on oath as follows:-

- DEPONENT

Identified by:

(Advocate, Shillong)

Bill of Quantity (BOQ)

Name of the Work: - Renovation of Police Outpost Office Including Civil, Plumbing and Painting Works

Sl no	Description	Unit	Quantity
1	Demolishing cement concrete including disposal of material within 50 metres lead as per direction of Engineer-in-charge a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	82.33
2	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	Cum	4.01
3	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead a) For thickness of tiles 10 mm to 25 mm	Sqm	58.20
4	Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead: b) 100 mm dia. Pipe	Rm	180.00
5	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge: a) 15 mm to 40 mm nominal bore	Rm	130.00
6	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead: a) Of area 3 sqm and below	Each	32.00
7	Providing soling with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete b) Stone soling (i) 100mm	Sqm	6.00
8	Cement concrete floor topping 1:1:2 (1 cement: 1 coarse sand: 2 stone aggregate) finished with a floating coat of neat cement, including cement slurry, complete b) 20 mm thick	Sqm	511.05
9	20 mm cement plaster of mix: a 1:4 (1 cement: 4 fine sand)	Sqm	511.05
10	Applying one coat of water thinnable cement primer of approved brand and manufacture on surfaces: Water thinnable cement primer	Sqm	473.25
11	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 ltr/10 sqm. One coat of self priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface	Sqm	473.25
12	Surface preparation: a) Removing existing white or colour wash on wall surfaces by steel wire brushing and/ or scraping, sand papering and preparing the surface smooth including necessary repairs to scratches complete.	Sqm	3338.68
13	Providing and applying Plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete	Sqm	2424.36
14	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: Old work (one or more coats)	Sqm	4848.72
15	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: b) Old work (one or more coats)	Sqm	243.36
16	Finishing walls with Acrylic Smooth exterior paint of required shade, including scaffolding: c) Old work (One or more coat applied @ 0.90 ltr/10 sqm)	Sqm	2268.00
17	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	324.24
18	Providing corrugated G.S or galvanised iron sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. e) 0.55 mm thick with zinc coating not less than 275 gm/sqm	Sqm	20.25
19	Supplying, fitting and fixing in position reinforcement bars upto 1st floor level, conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (Rates inclusive of all wastage, lappage, hooks, chairs, anchorage etc. and no measurement for the same is required) b) High Yield Strength Deformed bars or Tor Bars	Qntls	0.087

20	SHUTTERING/ FORMWORK Foundations, footings, bases of columns, etc. for mass concrete (using steel)	Sqm	1.50
21	Edges of slabs and breaks in floors and walls (using timber) b) Above 20 cm wide	Sqm	13.50
22	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement- All work up to plinth level: a) M15 or Prop. 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	Cum	8.55
23	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1cement:4 coarse sand) b) Granite of any colour and shade ii Area of slab over 0.50 sqm	Sqm	1.75
24	Providing and fixing 12 mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick a) Marine plywood conforming to IS:710	Sqm	6.72
25	Providing & Fixing decorative high pressure laminated sheet of plain/ wood grain in gloss/ matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS:2046 Type S, including cost of adhesive of approved quality.	Sqm	1.75
26	Providing and fixing ISI marked, IS:1341, M.S. heavy weight butt hinges with necessary screws etc. complete: b) 100x75x3.50 mm	Each	44.00
27	Providing and fixing ISI marked oxidised M.S. Handles conforming to IS:4992 with necessary screws etc. complete: c) 75 mm	Each	22.00
28	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required diameter and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc.	Kg	620.99
29	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: a) 125 mm	Each	73.00
30	Providing and fixing bright finished brass door latch with necessary screws etc. complete: a) 300x16x5 mm	Each	4.00
31	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge: c) With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	Sqm	28.80
32	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebated to be measured).Panelling for panelled and glazed shutters 25mm to 40mm thick: Pre-laminated with decorative lamination on both side exterior Grade-I MDF Board 12 mm thick confirming to IS:14587	Sqm	12.60
33	Providing polished VITRIFIED wall tiles of approved quality, size, shape and thickness not less than 8mm on walls and skirting over cement mortar bed 10 mm thick in prop. 1:3 (1cement: 3 coarse sand) including cutting where necessary finished with flush pointing with adhesive or white cement slurry mixed with approved pigment to match shade of tiles complete at all levels as specified and directed a) Normal range	Sqm	45.00
34	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS:15622, of approved make, in all colours and shades laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry@ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete a) Size of Tile 500x500 mm	Sqm	28.32
35	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge External work (vi) 50 mm nominal outer diameter Pipes	Rm	150.00
36	40 mm CPVC Pipes	Rm	30.00
37	25 mm CPVC Pipe	Rm	150.00

38	20 mm CPVC Pipes (Internal)	Rm	250.00
39	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete: c) 25 mm nominal bore	Each	20.00
40	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms a) 15 mm nominal bore	Each	25.00
41	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 a) 15 mm nominal bore	Each	65.00
42	Providing and fixing wash basin with C.I. brackets, 15 mm dia. CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets:- China Wash basin size 550x400 mm with a 15mm CP Brass single hole basin mixer White Vitreous	Each	12.00
43	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings.	Each	12.00
44	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer-in-charge.	Each	15.00
45	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required: a) Kitchen sink with drain board (i) 510x1040 mm bowl depth 250 mm	Each	2.00
46	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour.	Each	35.00
47	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete b) Flexible pipe	Each	30.00
48	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet: b 150 mm diameter	Each	8.00
49	Providing and fixing C.P. Brass extension nipple (size 15x50mm) of approved make and quality as per direction of Engineer-in-charge.	Each	120.00
50	Providing and fixing 8 mm dia. C.P/ S.S Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer-in-charge.	Each	8.00
51	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: a) W.C. pan with ISI marked white solid plastic seat and lid	Each	8.00
52	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour b) 15 mm nominal bore with 45 cm length	Each	80.00
53	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS:5382, leaving 10mm gap for thermal expansion, (i) Single socketed pipes b) 110 mm diameter	Rm	220.00
54	45degree PVC bend 110mm dia.	Each	38.00
55	PVC single tee with door 110mm dia.	Each	42.00
56	PVC coupler 110mm dia.	Each	69.00
57	87.5 degree PVC bend 110mm dia.	Each	75.00
58	PVC Plain single tee 110mm dia.	Each	30.00
59	87.5 degree PVC bend with door 110mm dia.	Each	28.00
60	Loading & Unloading of Stone	Cum	18.45
61	Loading & Unloading of Sand	Cum	10.68
62	Cost of Haulage (Excluding Loading & Unloading) of Materials	Tkm	1993.83