



North Eastern Indira Gandhi Regional Institute of Health and Medical Sciences  
(An Autonomous Institute, Ministry of Health and Family Welfare, Government of India)  
Director's Block, Mawdiangdiang, Shillong 793 018 (Meghalaya)  
**Website:** [www.neigrihms.gov.in](http://www.neigrihms.gov.in)

**Tender No: CVENGG-ESTI/4/2025-Engg(C);**

**Dated: 13<sup>th</sup> April, 2026**

## **TENDER /BID DOCUMENT**

**ONLINE OPEN E- TENDER ARE INVITED FROM REGISTERED CONTRACTORS  
OF PWD/ PHE/ ESTATE OFFICE (GAD)/ MES/ MeECL AND EQUIVALENT CLASS  
OF CPWD FOR CONSTRUCTION OF PUMP OPERATOR'S SHED ETC  
(e -Procurement)**

Bid Document Downloading Start Date:	1400 hours of 14.4.2026
Last Date and Time for Submission of Bid Document Online:	1400 hours of 4.5.2026
Last date and Time of Receipt of Earnest Money Deposit (hard copies):	1400 hours of 4.5.2026
Date and Time of Opening of Techno -Commercial Bids:	1400 hours of 5.5.2026
Cost of Earnest Money Deposit (EMD):	Rs.42,620.00

Bidders /Tenderers can download the tender /bid document from Central Public Procurement Portal website at [www.eprocure.gov.in](http://www.eprocure.gov.in) Bidders /Tenderers are required to submit their bid online by uploading all the relevant documents through [www.eprocure.gov.in](http://www.eprocure.gov.in)

Tender document can also be downloaded from the Institute's website at [www.neigrihms.gov.in](http://www.neigrihms.gov.in) For further details regarding amendment /addendum /extension please visit website: [www.eprocure.gov.in](http://www.eprocure.gov.in) and [www.neigrihms.gov.in](http://www.neigrihms.gov.in)

In the event of the date being declared as a closed holiday for purchaser's office, the due date for submission of bids online and opening of bids online will be the following working day at the appointed time.

## DETAILED TENDER NOTICE

Online tenders in two bid systems are invited from registered contractors of PWD/PHE/Estate office (GAD)/MES/MeECL and equivalent class of CPWD for the following work.

Name of work	Estimated cost (Rs) (approx)	EMD (Rs)
Construction of Pump Operator's shed etc	Rs.21,30,679/-	Rs.42,620/-

### **General Conditions of Contract (GCC):**

1. Bidders /Tenderers would be required to register on the Central Public Procurement Portal at [www.eprocure.gov.in](http://www.eprocure.gov.in), using a valid Digital Signature Certificate (DSC) and valid email address to be able to participate in the bidding process. On registration with the Portal they will be provided with a user id and password by the system through which they can submit their bids online.
2. Digital Signature Certificate (DSC) may be obtained from any authorized agencies registered with the Certifying Authority (CA), through National Informatics Center (NIC) in India.
3. Bidders /Tenderers can download the bid document from Central Public Procurement Portal website at [www.eprocure.gov.in](http://www.eprocure.gov.in) Bidders /Tenderers are required to submit the tender documents online by scanning and uploading with all the relevant documents through [www.eprocure.gov.in](http://www.eprocure.gov.in)
4. Tender document can also be downloaded from the Institute's website at [www.neigrihms.gov.in](http://www.neigrihms.gov.in) For further details regarding Amendment /Addendum /Extension please visit website: [www.eprocure.gov.in](http://www.eprocure.gov.in) and [www.neigrihms.gov.in](http://www.neigrihms.gov.in)
5. **Earnest Money Deposit (EMD) in the form of Call deposit, Banker's Cheque, Fixed deposit or Demand draft, drawn in favour of NEIGRIHMS EMD Security Deposits** or Bank Guarantee of any Scheduled Bank, shall be scanned and submitted online, along with the Techno-commercial bid (Un priced Bid), within the period of tender online submission date and time and the original (hard copy) should be dropped in the tender box in the Engineering Section, Director's Block, Mawdiangdiang, NEIGRIHMS, Shillong -793018, **not later than the last date of e-submission of the tender**
6. The technical bids will be opened online by a committee of members duly constituted for the purpose at the time and date as specified in the tender document. All statements, documents, certificates, Affidavits, etc uploaded by the bidders will be verified and downloaded for technical evaluation and the result of technical bid evaluation will be displayed on [www.eprocure.gov.in](http://www.eprocure.gov.in) which can be seen by all bidders who participated in the tender.
7. The bidders should download the **BoQ.xls** from CPP Portal and filled in the blank spaces provided for mentioning the name of bidder and rates. Bidders cannot modify any other text or background shown in the BOQ template or replace it with any other copy of same **BOQ in .xls format**. NEIGRIHMS /Central Public Procurement Portal ([www.eprocure.gov.in](http://www.eprocure.gov.in)) will accept the BOQ template only and hence the rate should not be quoted in any other place except BOQ template.
8. The Financial bid (price bid) i.e. Bill of Quantity (BOQ) of only technically qualified bidders will be opened online by a committee of members and the result will be displayed on the [www.eprocure.gov.in](http://www.eprocure.gov.in) which can be seen by all bidders who participated in the tender.
9. **Contractor shall quote the rate of AT PAR or ABOVE the Meghalaya PWD Schedule of Rates for buildings 2021 – 22 / for Roads 2020 – 21 and as per prevailing market rate for the Non Schedule Items.**
10. **Institute will reject Bids with rates quoting BELOW, the estimated value put to tender, for scheduled items.**
11. The site is located at Mawdiangdiang
12. Time of completion: 6 (six) months from the date of issue of commencement order.
13. Contractors shall be deemed to have inspected and examined the site of work and its surroundings and familiarized themselves, before submitting the tenders.
14. Tenderers will have to submit copy of their registration, which is valid as on the last date of bid submission.
15. The contractor shall not sub-contract the work to sub-contractors or to any single sub-contractor. An undertaking by the contractor shall have to be submitted to this effect.
16. The successful contractor shall provide a performance security for his proper performance of the contract within 7 (seven) days from the date of receipt of letter of award. **The performance Security shall be in the form of FD/Call Deposit to be pledged in favour of NEIGRIHMS EMD Security Deposits.** The amount of the security shall be 5% (five percent) of the contract price. The performance security shall remain valid for a minimum period of sixty days beyond the date of completion of all contractual obligations and shall be returned to the contractor within 14 days after expiry of the performance security. If the contractor fails to perform the work as per terms and conditions of the contract, the performance security shall be forfeited at his own risk and responsibility.
17. If during the execution of the work the contractor encounters physical obstructions or physical conditions other than climatic conditions on the site, which obstructions or conditions were in his reasonable opinion not foreseeable by the contractor, the contractor shall forth with give notice thereof to the Superintending Engineer, NEIGRIHMS. On receipt of such notice, the SE shall, in his opinion feel that such obstructions/conditions could not have been reasonably foreseen by the contractor, after due consultation with the contractor determine any extension of time with no financial bearing to which the contractor is entitled.

18. During the execution of the works, the contractor shall keep the site reasonably free from all unnecessary obstructions and shall store or dispose of any contractors equipment and surplus materials and clear from the site any wreckage, rubbish or temporary works in consultation with the Sanitary Supt of the Institute.
19. Before issue of any completion certificate, the contractor shall clear away and remove from that part of the site to which the completion certificate relates all contractors' equipment, surplus material, rubbish and temporary works of every kind.
20. The contractor while employing labour should ensure that all the statutory labour laws and regulations are adhered to.
21. In the event of
  - a. The amount or nature of extra or additional work
  - b. Exceptionally adverse climatic conditions
  - c. Other special circumstances which may occur other than through a default or breach of contract by the contractor or for which he is responsible. Being such as fairly to entitle the contractor to extension of time for completion of the works or any section or part thereof, the Institute shall after due consultation with the contractor and subject to clause 17 determine the amount of such extension with no financial bearing and shall notify the contractor accordingly.
22. If the contractor fails to complete the execution and completion of the works as specified in the work order, the contractor shall be bound to pay as liquidated Damages a sum of 0.5 % (percent) per week of delay for such default subject to a maximum of 5 % of the contract price.
23. When whole of the works have been substantially completed, the contractor shall give a notice to the Superintending Engineer of the Institute, accompanied by a written undertaking to finish with due expedition any outstanding work during the defect Liability period. Such notice and undertaking shall be deemed to be a request by the contractor to the SE to issue a taking over certificate.
24. Defect liability period shall be 12 (twelve) months calculated from the date of completion of the works certified by the SE in the completion certificate.
25. The performance bank guarantee shall be kept valid for a period of 6(six) months after the DLP.
26. If the contractor fails to fulfill any of the obligations under this contract, the Institute shall be at liberty to terminate the contract thereby voiding the contract and will be at liberty to allot the whole work or balance works to any other party at the risk and cost of the first party.
27. All works are to be carried out as per current specification prevailing in the state of Meghalaya (MPWD & CPWD) and when directed by the Institute.
28. Institute is adopting Scheduled of Rates of Meghalaya State –PWD for roads & building. **There will be no price escalation whatsoever. The rates quoted by the successful bidder on acceptance by the Institute, will be binding and final.**
29. **Average Annual Financial Turnover** during the last five years ending 31<sup>st</sup> March of the previous financial year should be at least **30 % of the estimated cost**. Tenderer to submit Financial Statement from Chartered Accountant as per **FORMAT – B**.
30. Parties should have the experience of having successfully completed similar works during the last **5 (five) years** ending last day of month previous to the one in which applications are invited should be either of the following: (a). **Three similar completed works each** costing not less than the amount equal to **40% of the estimated cost** or (b) **Two similar completed works each** costing not less than the amount equal to **50 % of the estimated cost** or (c) **one similar completed work** costing not less than the amount equal to **80 % of the estimated cost**. Documentary proof in the form of completion certificates only are to be enclosed failing which the tender will be non-responsive.
31. Completion Certificates should indicate the items of works executed along with the date of award of work & time of completion as per work order & actual time of completion and are to be signed by Officers not below the rank of Executive Engineers or Equivalent (**FORMAT –A**)
32. **AVAILABLE BID CAPACITY**  
 Applicants who meet the minimum qualification criteria will be qualified only if their available bid capacity at the expected time of bidding is more than the total estimated cost of the work. The available bid capacity will be calculated as under:  
**Available Bid Capacity = (A x N x 2 – B)**, where:  
 A - Maximum value of works executed in any one year during the last five years (updated to the current price level). Rate of inflation may be taken as 10% per year which will take into account the completed as well as works in progress  
 B – Value of work at current price level of the existing commitment and outgoing work to be completed during the period of completion of work for which are invited.  
 N – Number of years prescribe for completion of the works for which the bid are invited is the number of years prescribed for completing the works
33. Running payments can be made to the contractor subject to certification by the Superintending Engineer after completion of about 50% of the work and final payment will be paid after completion of the work after due certification and satisfaction of the Superintending Engineer.
34. Parties to submit PAN Card, GST Registration, valid Labour License from Labour Department
35. Rates once accepted will not be enhanced due to variation in the rate of materials, labour and Government taxes.
36. Bidder should submit documents showing that they have enough plant and machineries. Undertaking in the form of affidavit to be submitted. No tools and plants will be supplied by the Institute
37. No materials will be supplied by the Institute.
38. The quoted rates shall be firm, fixed and binding on the contractor irrespective of any variation in the quantities stated in the contract upto ± 15 % variation of the contract value as a whole.

39. Successful Non –Tribal tenderers should submit the valid Trading license within 14 (fourteen) working days from the date of issue of preliminary work order, failing which the order shall be withdrawn at their risk and responsibility. Trading License submitted should be specifically for similar nature of work for which the tender is called for.
40. **In case of dispute:** It is agreed between the first party and the second party that all disputes, differences and claims whatsoever which shall arise at any time between the parties hereto or their respective representatives concerning this contract and all other documents in pursuance hereof as to the rights, duties, obligations or liabilities of the parties hereto respectively by virtue of this contract shall be referred to the Director of the Institute, which shall then take a final call on the matter and will be final and binding.
41. The specifications and mode of measurement for civil works shall be in accordance with PWD specifications unless otherwise specified and more specifically as per approved Drawing, Specification and Estimate.
42. **In the event of responsive parties quoting same rates and having same Available Bid Capacity, the Institute reserves the right to allot the work to the bidder having higher / highest credentials in terms of similar work experience, etc.**
43. If there is any excess payment on any item etc made to the contractor, the contractor shall not hesitate to cooperate in adjusting / deducting the same from either the running bills or final bills.
44. **The Institute reserves the right to accept or reject any or all tenders without assigning any reason thereof**
45. All the above requirements are compulsory for fulfillment as part of the tenders failing which tenders will be rejected.
46. All documents, registrations should be valid as on the last date of tender.
47. Taxes as applicable will be deducted from the bills of the contractor.
48. Parties to submit the list of technical staff with at least 1(one) experienced Junior Engineer-Civil (Diploma). Attested copy of diploma/degree certificates to be enclosed. Undertaking in the form of affidavit to be submitted.
49. The parties to furnish an affidavit on a non-judicial stamp paper that there is no police/vigilance/CBI case pending against them.
50. Successful bidder will have to furnish an Undertaking to carry out/ execute the work in strict conformity to the specifications as mentioned in the scheduled items and guide notes of the Scheduled of Rates and Indian Standard codes of practice for materials / as per direction of the Engineer-in-charge failing which he/she shall be liable for disqualification/ blacklisted from participating in future tenders of NEIGRIHMS
51. **The Party shall be responsible for the safety of all its workmen/employees during the period of execution of the work. The party shall provide all safety materials, insurance cover, gadgets, equipment etc to all its workmen/employees to ensure their safety during execution of the work. The Institute shall not be held responsible in case of any accidents, mishaps etc to the party and its employees**
52. Any delay in completion of the works beyond the stipulated date due to reasons attributable to the contractor may eventually lead to cancellation of letter of award for which the contractor is not entitled to any compensation. The cancellation of letter of award would lead to forfeiture of performance security.
53. **The contractor is to register with the Labour Department for the work and the registration certificate has to be submitted, failing which the bill cannot be processed**
54. If any statutory tax/deduction/recovery is notified by the State/Central Govt, the same shall be deducted from the bill of the contractors as applicable from its effective date of coming into force.
55. The Payment for the work done by the Contractor will be on the basis of measurement of the work executed. **The Contractor's Engineer or his authorized agent or representative shall be present at the time of recording of each set of measurements and sign on the measurement book as a token of acceptance of the measurement.**
56. Contractors who engage / employ five or more Inter State Migrant Workmen is required to obtain a license from District Labour Office, East Khasi Hills, Shillong as per prevailing labour laws applicable in the State.
57. Bidders should note that the above terms and conditions will apply specifically in addition to the rules / regulations applicable to works in the Government of India.
58. **All prevailing GFR rules will be applicable and binding.**
59. Wherever relevant, water charges @ 1% on the Order value will be as applicable or Contractor may arrange his / her own water supply with intimation to the Superintending Engineer.
60. Electricity charges when used by the Contractor will be deducted from the bill as per actual usage/consumption through tested meter in consultation with Electrical Department of the Institute or the Contractor may use his / her own DG sets in case of fabrication works etc , with intimation to the Superintending Engineer.
61. Forest Royalty of stone and sand shall be deducted as per latest / prevailing rate of Forest Department Government of Meghalaya
62. **In the event that structural / architectural design is required, the qualified bidder shall at his own cost provide the structural / architectural design from reputed structural engineers / firms and submit to the Institute for acceptance.**
63. **For works costing beyond Rs 2.00 Cr, the successful bidder / contractor will need to have a Quality Control Engineer.**
64. **For concrete / RCC works, contractor will have to carry out standard cube tests before and after casting of any RCC member at the cost of the contractor.**
65. **The court jurisdiction for any dispute, if not settled as per Clause 39, shall be at Shillong, Only.**

Sd/  
Superintending Engineer  
NEIGRIHMS

Copy to: Accounts officer for information

**Check List of documents to be submitted along with the tender:**

<b>SI No</b>	<b>Documents</b>	<b>Remarks</b>
1	Tender documents	
2	Earnest money Deposit	
3	Copy of registration	
4	Undertaking not to sub-let the work. (format enclosed with the tender)	
5	Pan Card.	
6	G S T certificate	
7	Valid Labour License	
8	Documentary proof of work orders, completion certificates as specified in clause 28 of the GCC.	
9	Completion certificates as per FORMAT – A	
10	Average Annual Financial Turnover during the last five years as per FORMAT - B	
11	List of technical staff with Undertaking in the form of affidavit (Degree/Diploma certificate to be enclosed)	
12	Affidavit of no vigilance/police/CBI case pending against them	
13	Plant and machineries. Undertaking in the form of affidavit	

**FORM OF UNDERTAKING**

To

The Superintending Engineer  
NEIGRIHMS

Sub: Construction of Pump Operator's shed etc

Sir,

With reference to the above, I hereby undertake not to sublet the work cited above, if the work is allotted to me.

Date:

*Name of contractor	
*Full postal Address	
*Email Address	
*Mobile No	
*Alternate Mobile No	
*Signature and Seal	

All the fields marked \* above are mandatory to be furnished by the contractor

**FORMAT - A.**

1. Name of Contractor: - .....
2. Name of work completed: - .....
3. Agreement No: - .....
4. Name of Division in which work was executed: - .....
5. Tender Cost: - .....
6. Stipulated date of Start (as per w/o):- .....
7. Stipulated date of Completion (as per w/o):- .....
8. Actual date of Completion: - .....

Signature of Contractor

\*\*Signature of Officer issuing the C/Certificate

\*\* (Officer should not be lower than the rank of Executive Engineer – Civil)

**FORMAT B**

**FINANCIAL STATEMENT**

<b>SL NO</b>	<b>FINANCIAL PERIOD</b>	<b>AMOUNTS IN LAKHS</b>
<b>1.</b>	<b>2020 – 2021</b>	
<b>2.</b>	<b>2021 – 2022</b>	
<b>3.</b>	<b>2022 - 2023</b>	
<b>4.</b>	<b>2023 - 2024</b>	
<b>5.</b>	<b>2024 - 2025</b>	

SIGNATURE OF  
CONTRACTOR

SIGNATURE OF  
CHARTERED ACCOUNTANT

**BEFORE THE MAGISTRATE FIRST CLASS IN SHILLONG  
AFFIDAVIT**

I, Shri \_\_\_\_\_, son of Shri \_\_\_\_\_ aged about \_\_\_\_\_, resident of \_\_\_\_\_  
\_\_\_\_\_ do hereby solemnly affirm and declare on oath as follows:-

1. That I am a bonafide citizen of India and a permanent of the above – mentioned address.
2. That I am a registered contractor, with \_\_\_\_\_vide Reg. No. \_\_\_\_\_.
3. That there is no police / vigilance/ CBI case pending against me/ firm.
4. That I have not been blacklisted in the past by any Government or Private Organization.
5. That the instant affidavit is sworn in for the purpose of giving a declaration of the aforesaid facts and for all other purpose and intents.
6. That the statements made herein above are true to the best of my knowledge, belief and information.

DEPONENT

Solemnly affirmed and declared before me the Deponent above named who is identified by \_\_\_\_\_ Advocate, Shillong on this the \_\_\_\_\_ at Shillong.

Identified by:

MAGISTRATE FIRST CLASS  
SHILLONG

(Advocate, Shillong)

## Bill of Quantity

Name of the Work: - Construction of Pump Operator's shed etc

SI No	Description	Unit	Quantity
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	Sqm	179.00
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge	Cum	0.80
3	Earthwork in excavation by manual means upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/ walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classification of soils. All kinds of soil (ordinary soil/ hard soil/dense soil) In ordinary rock (soft rock/ medium rock/ hard shale) b) In ordinary rock (soft rock/ medium rock/ hard shale)	Cum	100.823
4	Providing soling with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete. b) Stone soling i) 100mm	Sqm	107.85
5	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement: 6 coarse sand:12 graded stone aggregate 20 mm nominal size) upto plinth level with: a) Cement mortar 1:6 (1 cement:6 coarse sand)	Cum	70.168
6	Plain cement concrete works in foundation bed for footing steps, walls, brick works etc below plinth level as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately). b) 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size)	Cum	10.266
7	Supplying, fitting and fixing in position reinforcement bars upto 1st floor level, conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (Rates inclusive of all wastage, lappage, hooks, chairs, anchorage etc. and no measurement for the same is required) b) High Yield Strength Deformed bars or Tor Bars	Qntl	16.07
8	SHUTTERING/ FORMWORK Centering and shuttering including strutting, propping etc. and removal of form for all heights complete and as directed by Engineer in charge. Columns, Pillars, Piers, Abutments, Posts and Struts (using steel)	Sqm	109.86
9	SHUTTERING/ FORMWORK Centering and shuttering including strutting, propping etc. and removal of form for all heights complete and as directed by Engineer in charge Lintels, beams, plinth beams, girders, bressumers and cantilevers (using steel)	Sqm	20.25
10	SHUTTERING/ FORMWORK Centering and shuttering including strutting, propping etc. and removal of form for all heights complete and as directed by Engineer in charge Slabs, roofs, landings, balconies and access platform, shelves (using steel)	Sqm	37.50
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement- All work up to plinth level: a) M15 or Prop. 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	Cum	15.57
12	Earthwork in filling (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm thick including breaking of clods, consolidating each layer by ramming and watering, lead upto 50 m and lift upto 1.5 m . b) With borrowed earth/stone dust carriage upto 5 Km	Sqm	9.72
13	Cement concrete floor topping 1:1:2 (1 cement: 1 coarse sand: 2 stone aggregate) finished with a floating coat of neat cement, including cement slurry, complete. a) 15 mm thick	Sqm	10.80

14	Half brick masonry with common burnt clay (non modular) 1 <sup>st</sup> class bricks in foundations and in plinth: a) Cement mortar 1:3 (1 cement:3 coarse sand)	Sqm	102.205
15	15 mm cement plaster on the rough side of single or half brick wall of mix: a) 1:4 (1 cement: 4 fine sand)	Sqm	233.755
16	12 mm cement plaster finished with a floating coat of neat cement of mix: a) 1:3 (1 cement: 3 fine sand)	Sqm	438.77
17	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5 mm or 35x5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-in-charge	Kg	213.072
18	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with: a) 4.0 mm thick glass panes	Sqm	7.26
19	Providing beams including hoisting, fixing in position and applying wood preservative for the unexposed surfaces, etc. complete with: b With 1st Class Local wood (Pooma/ Hollock/ Gamari/ and the like)	Cum	0.0714
20	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part I) decorative type, core of block board construction with frame of 1stclass hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. a) 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	3.78
21	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	2860.92
22	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	1381.693
23	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: a) New work (two or more coats over an under coat of suitable shade with ordinary paint of approved brand and manufacture)	Sqm	106.6056
24	Applying one coat of water thinnable cement primer of approved brand and manufacture on surfaces: Water thinnable cement primer	Sqm	171.40
25	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: New work (two or more coats)	Sqm	171.40
26	Providing corrugated G.S or galvanised iron sheet roofing including vertical/ curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. e) 0.55 mm thick with zinc coating not less than 275 gm/sqm	Sqm	39.44
27	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia. G.I. limpet and bitumen washers complete d) 0.55 mm thick with zinc coating not less than 275 gm/sqm	Rm	5.00
28	Providing and fixing 15cm wide, 45 cm overall semi-circular plain G.S. sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers, etc., including making necessary connections with rain water pipes complete. a) 0.80 mm thick with zinc coating not less than 275 gm/sqm	Rm	8.00
29	Providing and installing false ceiling at all heights including providing and fixing of frame work with 9 mm thick Gypsum tile with prelude grid complete as per directions of Engineer-in-Charge	Sqm	10.80
30	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement:4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels b Granite of any colour and shade ii Area of slab over 0.50 sqm	Sqm	1.50

31	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required diameter & length b Sal wood	Cum	0.0245
32	Providing and fixing 12 mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick b Fire retardant plywood conforming to IS:5509	Sqm	3.00
33	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: k) Stainless Steel AISI-304(18/8) Wash basin 530x345 mm with single 15 mm C.P. brass pillar tap	Each	1
34	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: a) 300 x 10 mm	Each	7
35	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. complete: c) 100 x 75 x 4 mm	Each	24
36	Providing and fixing chromium plated brass handles with necessary screws etc. complete: a) 125 mm	Each	7
37	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work (ii) 20 mm nominal outer diameter Pipes	Rm	15.00
38	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS:5382, leaving 10mm gap for thermal expansion, (i) Single socketed pipes a) 75 mm diameter	Rm	7.00
39	Providing and fixing brass bib cock of approved quality: b) 20 mm nominal bore	Each	1
40	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 25x25 mm made of G.I. wire of dia. 3 mm including strengthening with 2 mm dia. wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge	Sqm	37.50
41	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. a) With G.I. barbed wire	Sqm	30.00
42	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours and shades of any size as approved by Engineer-in-Charge, in walls, skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete a) Normal range	Sqm	13.50

43	<p>Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19x19 mm for stiles and 15x15 mm for top &amp; bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming stiles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail &amp; bottom rail, panelling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the stiles&amp; rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification &amp; drawing.</p> <p>a) 30 mm thick plain PVC door shutters</p>	Sqm	2.00
44	<p>Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand Cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS:7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:</p> <p>a) White Vitreous china Orissa pattern W.C. pan of size 580 x 440 mm with integral type foot rests</p>	Each	1
45	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot &amp; cold water supply, including all CPVC plain &amp; brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes &amp; fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge</p> <p>Internal work - Exposed on wall</p> <p>(ii) 20 mm nominal outer diameter Pipes</p>	Rm	8.00